

Average Unit Rates Compiled From Recent Contractor Bids

| ITEMIZED DESCRIPTION | UNIT | AVERAGE UNIT COST |
|---|------|-------------------|
| 02510 - ROADWAY IMPROVEMENTS | | |
| Mass Grade Fill - short haul | CY | \$1.43 |
| Mass Grade Cut - short haul | CY | \$1.48 |
| Subgrade Prep for Roadways (5' Behind ROW Ea. Side) | SQFT | \$0.12 |
| 3" PG 64-22 Asphalt (Pavement Section) | SQFT | \$1.15 |
| 5" PG 64-22 Asphalt (Pavement Section) | SQFT | \$2.00 |
| 8" Granular Base Course, Lip to Lip | SQFT | \$0.51 |
| 10" Granular Base Course, Lip to Lip | SQFT | \$0.60 |
| Roadway Over excavation and Import (25% for 18" TBC to TBC) | CY | \$16.33 |
| 2.5-foot Curb and Gutter with Base Course | LNFT | \$13.90 |
| 5' wide Sidewalk (5" thick) with Base Course | LNFT | \$21.50 |
| 8' wide Sidewalk (5" thick) with Base Course | LNFT | \$33.00 |
| Sidewalk Handicap Ramps W/ Base Course | EACH | \$534.00 |
| Lane 6" Granular Base Course ROW to ROW | SQFT | \$0.55 |
| Lane 6" 4000 psi Concrete | SQFT | \$3.10 |
| Lane Drive Approach with Base Course | EACH | \$1,650.00 |
| Demo Existing Curb & Gutter | LNFT | \$3.83 |
| 02665 - DOMESTIC WATER SYSTEMS | | |
| 6" C-900 Pipe | LNFT | \$18.50 |
| 8" C-900 Pipe | LNFT | \$25.00 |
| 12" CLASS 52 DI Pipe | LNFT | \$43.00 |
| 8" Gate Valves with valve box/cover | EACH | \$1,600.00 |
| Fire Hydrant Assembly (Includes Valve & Piping) | EACH | \$4,500.00 |
| 3/4" Service Connections with 3/4" meters | EACH | \$1,200.00 |
| 1" Service Connection with 3/4" meter | EACH | \$1,350.00 |
| 2" Blow Off Assembly | EACH | \$1,448.00 |
| 8" Tie-ins to existing system | EACH | \$1,350.00 |
| 02667 - SECONDARY IRRIGATION SYSTEMS | | |
| 2" C-900 | LNFT | \$33.00 |
| 6" C-900 | LNFT | \$19.50 |
| 8" C-900 | LNFT | \$20.00 |
| 2" Meter Irrigation Point of Connection (P.O.C.) | EACH | \$3,500.00 |
| 02721 - STORM DRAINAGE SYSTEMS | | |
| 15" RCP CLIII Pipe | LNFT | \$45.00 |
| 24" RCP CLIII Pipe | LNFT | \$51.00 |
| Catch Basin | EACH | \$2,500.00 |
| 5' Storm Drain Cleanout | EACH | \$2,950.00 |
| Dry Well | EACH | \$19,500.00 |
| 8.5' Storm Drain Gallery | CF | \$2.95 |
| 12' Storm Drain Gallery | CF | \$4.90 |
| 12' Storm Drain Gallery - Deep Excavation | CF | \$6.30 |
| Stub and Plug | EACH | \$500.00 |
| 02722 - SANITARY SEWER SYSTEMS | | |
| 8" PVC Sewer Line | LNFT | \$31.00 |
| 12" PVC Sewer Line | LNFT | \$36.00 |
| 4' Manhole w/ Collar | EACH | \$3,300.00 |
| 5' Manhole w/ Collar | EACH | \$3,900.00 |
| 4" Service Laterals (Housing Only) | EACH | \$1,200.00 |
| Stub and Plug | EACH | \$400.00 |
| Tie to existing | EACH | \$1,100.00 |

Average Unit Rates Compiled From Recent Contractor Bids

| ITEMIZED DESCRIPTION | UNIT | AVERAGE UNIT COST |
|---|------|-------------------|
| 02813 - ELEC, SIGNS, STRIPES & EROSION CONTROL | | |
| Electrical/Dry Utilities (Estimated) | | |
| CAT 3 Lights w/Poles | EACH | \$6,600.00 |
| CAT 4 Lights w/ Poles | EACH | \$6,200.00 |
| Junction Boxes | EACH | \$170.00 |
| 2 Gauge Wire (1) | LNFT | \$3.00 |
| 4 Gauge Wire (1) | LNFT | \$2.25 |
| 6 Gauge Wire (1) | LNFT | \$1.40 |
| 2" Conduit - Along Street (1) | LNFT | \$4.00 |
| Joint trench crossings for dry utilities | | |
| 2" Conduit | LNFT | \$2.70 |
| 4" Conduit | LNFT | \$3.85 |
| 6" Conduit | LNFT | \$5.50 |
| 8" conduit | LNFT | \$11.50 |
| Signage & Striping | | |
| R1-1 Stop Sign | EACH | \$350.00 |
| Street Name Signs | EACH | \$350.00 |
| Striping | | |
| Stop Bar Markings (Thermoplastic Tape) | LNFT | \$16.00 |
| Cross walk (Thermoplastic Tape) | LNFT | \$16.00 |
| 4" White Solid | LNFT | \$0.65 |
| 4" Yellow Solid | LNFT | \$0.65 |
| Pavement Arrows | EACH | \$500.00 |
| Erosion Control | | |
| Stabilized Construction Entrance Maintenance | LPSM | \$2,000.00 |
| Filter Sock Inlet Protection | EACH | \$55.00 |
| 02814 - MISCELLANEOUS | | |
| Survey Monumentation | EACH | \$650.00 |